

**Brockton High School
Auditorium and TV Studio Systems Renovation**

**Contract/Bid Number 2080-0005
Bid RFI -001**

No. Question

General

- Will we be able to submit questions after walk-thru on 6/26 even though deadline for written questions is the day before the walk-thru on 6/25?
- Q1 Yes. E-mail all remaining final written questions by Thursday morning 6/27 at 10AM.
- A1 They will be answered on 6/28

Auditorium Lighting Systems

- Specification 110640 quantities seem to be duplicated. Section 2.12. A.1 reads "all units to include 10' DMX". This would result in a Quantity of 121, then in Section 2.14 C.1.a there is a quantity of 10' DMX = Quantity: 90
- Q2
- A2 Provide ninety (90) 10'-0" DMX Extension Cables
- Q3 Specification 110640 Section 2.16. What type of base are you looking for the 500/700's retrofits ? Standard 3000k chip? Reflector type?
- A3 The specification correctly states the base, color temperature and reflector type within Section 2.16

Auditorium AV Systems

- There is no mention of projection screen? Is there an existing screen? Where is it located and how is it controlled?
- Q4 What is the distance from projector to screen so we can determine the correct lens.
- A4 There is an existing screen. The screen is controlled manually with a switch that is side stage. Location, distance a size can be measured on site during the walkthrough

TV Studio System

- 274116 Section 2.11 and 2.12 appear to specify the same equipment for both Teleprompter and Tally Light. Is the teleprompter system
- Q5
- A5 YES. Provide a Prompter People Pro-FS19, 19-inch teleprompter as basis of design. Provide with adjustable beamsplitter angle, Flip-Q Pro Prompting software. Provide complete with stand and optional iPad Bracket
- Q6 There aren't any lighting fixtures listed at all for the studio. Are they using exiting fixtures?
- A6 Replacement Studio lighting fixtures are not part of this project. They are using existing fixtures